# EXIT PLAN NOTES:


- 1. PER 1006.2.1 TRAVEL DISTANCE TO COMMON PATH OF TRAVEL W/ SPRINKLER SYSTEM < 100'-0' (OK)
- 2. PER 1017.2 OVERALL EXIT TRAVEL DISTANCE < 250'-0' WITH SPRINKLERS FOR (A OCC.) (OK)
- 3. EXITS ARE ALL GREATER THAN 1/3 THE DIAGONAL DISTANCE APART WHERE THERE IS REQUIRED TO BE MORE THAN ONE EXIT.
- 4. PER 1005 EGRESS WIDTH PER OCCUPANT SERVED XX OCCUPANTS (PER COVER SHEET) (.20) INCHES PER OCCUPANT (PER TABLE 1005.1 WITH (A) OCCUPANCIES XX X (20) = X' WE PROVIDE 5 EXIT DOORS X (34') = 170' WHICH IS > X' (OK)
- 5. MINIMUM NUMBER OF EXITS FOR OCCUPANT LOAD (SECTION 1019.1) OCCUPANT LOAD IS X AND FOR OCCUPANT LOADS < 500 OCCUPANTS TWO EXITS REQUIRED (5) EXITS ARE PROVIDED AND DOORS SWING OUT. (OK)
- 6. INSTALL EXIT LIGHTS & FIRE EXTINGUISHERS SHOWN ON PLAN AND AS DIRECTED BY THE FIRE MARSHALL

FLOOR PLAN NOTES: 1. CONFIRM ALL ROUGH OPENINGS FOR DOORS AND WINDOWS PRIOR TO FRAMING AND ORDERING.

2. SEE METAL BUILDING DRAWINGS FOR LOCATION AND INFORMATION ON STEEL MAIN FRAMES AND BASE PLATES.

Í	FLOOR PLAN LEGEND
EXIT	DIRECTIONAL EMERGENCY EXIT SIGN HARDWIRE W/ BATTERY BACKUP
	COMBINATION EXIT SIGN/EMERGENCY LIGHTING WITH BATTERY BACKUP HARDWARE
	EMERGENCY LIGHTING W/ BATTERY BACKUP HARDWARE
●FE	2A 10BC FIRE EXTINGUISHER SEE FLOOR PLAN FOR LOCATIONS 75 FEET MAX TRAVEL DISTANCE
$\langle x \rangle$	DOOR NUMBER SEE SHEET A-2.3 FOR SCHEDULE
$\Rightarrow$	WINDOW NUMBER SEE SHEET A-2.3 FOR SCHEDULE
XXX	ROOM FINISH TAG SEE SHEET A-2.3 FOR SCHEDULE
D.S.	DOWNSPOUT CONNECT TO CIVIL TIGHTLINE TYP.
• •	METAL BUILDING MAIN FRAME (SEE METAL BUILDING DRAWINGS)
	EXTERIOR METAL BUILDING 24 GA. MTL. SIDING O/ R-21 CONTINUOUS PIP RIGID INSULATION, TAPE ALL SEAMS TYP. O/ 8-1/2' MIN. 'Z' GIRTS PER MTL. BLDG. SUPPLIER (MANF. TO VERIFY SIZE/GAUGE)
	INTERIOR 6' OR 3-5/8' STEEL STUDS 30 MIL @ 16' O.C. W/ R-11 SOUND BATT INSULATION W/ <sup>5</sup> /8' GWB EA. SIDE, FRAME TO CEILING ABOVE TYP.
R. 4>	(2) TOTAL 175,000 BTU GAS UNIT REZNOR HEATER SUPPORT FROM FRAMES ABOVE W/ UNISTRUT GAS LINE TO HEATERS TO BE 1-1/4' BLACK PIPE TO EA. LOCATION SEPARATE LINES FOR EACH UNIT. MAX. LENGTH OF PIPE TO BE 225'

C



Concept #1 - Enclosed Building - Preliminary Layout Drawing for Budget Purposes

	Ý			
CARLETT	'I ARCI	HITEC	CTS	P.S.
arch	itecture &	. p <b>lanni</b> r	g	
116 EAST SUITE A MOUNT V				'3
Phone: Fax:	(360) (360)	124-0 124-5	394 726	

A NEW FACILITY FOR: SUDDEN VALLEY BARN 6 REPLACEMENT 98229

22-607 PROJE	CT NUMBER:
REVISI	ONS:
2-3-21	PRELIM. SET
SHEET	TITLE:
	PLAN

PJC PROJECT ARCHITECT DAVID WILSON DRAWN BY:

PJC CHECKED BY:

JANUARY 31, 2022 Date

S:/ARCH/22-607 SVBARN6 COMPUTER FILE NAME

COPYRIGHT 2022 CARLETTI ARCHITECTS, P.S.



Concept #1 - Enclosed Building Preliminary Budget

4.01.2022

## Sudden Valley Barn 6 New Construction of 13,000 S.F. Facility

CSI Division	Division Title		Total
	Facility Construction		
2	Existing Conditions	\$	126,320.00
3	Concrete	\$	268,885.00
5	Metal	\$	36,530.00
6	Woods, Plastics & Composites	\$	6,120.00
7	Thermal & Moisture Protection	\$	49,745.00
8	Openings	\$	69,938.00
9	Finishes	\$	19,868.00
10	Specialties	\$	11,450.00
13	Special Construction	\$	419,874.00
14	Equipment	\$	9,368.00
	Facility Services	•	
21	Fire Suppression	\$	67,093.00
22	Plumbing	\$	30,014.00
23	HVAC	\$	59,960.00
26	Electrical	\$	141,437.00
01	Site and Infrastructure	ተ	00 717 00
31	Earthwork	\$	93,717.23
	Hard Costs	\$ 1	,410,319.23
	General Requirements 12%	\$	169,238.31
	GC Overhead & Profit 10%	\$	157,955.75
	Subtotal	\$ 1	,737,513.29
	Estimate Contingency 15%	\$	260,626.99
	Subtotal	\$ 1	,998,140.29
	WSST 8.8%	\$	175,836.35
	Grand Total	\$ 2	2,173,976.63



May 22, 2023

Sudden Valley Community Association Attn: Jo Anne Jensen 4 Clubhouse Circle Bellingham, WA 98229

#### RE: Project Summary Capital Project 9723.06 – Marina Dock Replacement

On 3-9-23 SVCA's Board approved Capital Code 9723.06 for the Marina Dock Replacement project. In 2027 the wet slip docks are proposed to be replaced, and a budget of \$187,177.00 was identified in the reserve study. Following approval of Capital Code 9723.06 SVCA retained Ashton Engineering to complete the preliminary design and engineer's estimate.

Ashton Engineering completed the preliminary design per the attached layout drawings dated 4-21-23. An engineer's estimate was also completed per the attachment dated 4-24-23. A few notes on the design:

- The new design adds 4 additional wet slips bringing the total up to 92 slips.
- Water and electrical services have been added to the slips as shown in the drawings.
- The design is ADA compliant with 4 slips identified for ADA use on the West Dock. The ADA slips are shown closest to the gangway on both sides of the 5' finger docks.
- The existing pilings are assumed to be reused.
- The West dock will receive a new gangway to meet ADA requirements, and the East dock gangway will be reused.
- Existing security gates will be reused.

•

Overall summary of anticipated costs:

Design, Permitting, and Contractor Bids	
- Design & Engineering – Ashton Engineering Estimate	\$25,000.00
- Survey Allowance	\$10,000.00
- Permit Fees Allowance	\$20,000.00
- PNW Services, Inc. – Per Attached Estimate	\$5,400.00
Subtotal Design, Permitting, and Contractor Bids	\$60,400.00
Construction Estimate	
- PNW Services, Inc. – Construction Management Estimate Per	\$5,400.00
Attached	
- Ashton Engineering – Construction Management Allowance (80	\$13,760.00
Hours at \$172.00)	
- Engineer's Estimate – Ashton Engineering (Includes 15%	\$1,304,133.00
Contingency)	
- WSST @ 8.6%	\$112,155.44
Subtotal Construction Estimate	1,435,448.44
Total Base Bid Estimate Design & Construction	\$1,495,848.44

•




The above estimate is based on 2023 pricing information. SVCA should add a contingency allowance for inflation and material escalation given the project is scheduled to take place in 2027.

Please let me know if you have any questions, or if you would like any further information.

Sincerely,

Tyler Andrews President

•



Scale: 1" = 30 ft







West Dock Gangway and Gate





East Dock Gangway and Gate Scale: 1" = 30 ft





Scale: 1" = 30 ft

#### NOTES FOR WEST AND EAST DOCK

PRELIMINARY PLANS FOR COST ESTIMATING PURPOSES.

DIMENSIONS OF FINGERS AND WALKWAY ARE NOMINAL WITHOUT TRIM OR STRUCTURAL WALES.

WIND: 110 MPH 3SEC GUST UNOCCUPIED DOCKS. 85 MPH 3SEC GUST OCCUPIED DOCKS WITH 22' BOATS. DOCK VERTICAL LIVE LOAD = 25 PSF. 300 LB CONCENTRATED LOAD. DEAD LOAD FREEBOARD = 14" TO 16". ALUMINUM GANGWAY LIVE LOAD = 100PSF WITH MAX L/360 DEFLECTION. 20 PSF GANGWAY LOAD FOR FLOTATION DESIGN.

WAVE: 1' WAVE HEIGHT

ALUMINUM OR PAINTED STEEL FRAMED DOCKS WITH ENCASED FLOTATION SHALL HAVE GRATING ABOVE AREAS WITHOUT FLOATATION. PLASTIC LUMBER MAY BE USED ABOVE FLOAT TUBS.

FLOAT TUBS SHALL BE FULLY ENCASED IN POLYETHYLENE SHELLS.

GRATING SHALL BE FIBERGRATE MICRO-MESH GRATING OR APPROVED SUBSTITUTE.

USE UHMW RUB MATERIAL AT PILE GUIDES.


NO GALVANIZED STEEL OR PRESSURE TREATED WOOD IS ALLOWED.

5' WIDE FINGERS ARE FOR ADA ACCESS. FOUR ADA ACCESS SLIPS - WEST DOCK ONLY.

REUSE EXISTING DRY STANPIPE COMPONENTS AS MUCH AS POSSIBLE. SEE DRAWINGS FOR EXISTING STANDPIPE SYSTEM.

REUSE AND RELOCATE SECURITY GATES. REWIRE AS NECESSARY.


REUSE EAST DOCK GANGWAY AND ABUTMENT.







810 Mapleridge Dr. Everson, WA 98247 360.510.7946



This is an Opinion of Probable Cost

ASHTON	DATE:	4.24.2023 Revised to include electrical and water at fingers.	
	A/ E:	Ashton Engineering, Inc.	
Engineering, Inc. Coastal & Stractural Design	ESTIMATE:	Preliminary Design Budgetary Estimate	
	BY:	Rory Woolsey, CEP	
	SPECIFICS:	Replace Floating West Docks (46 Slips) and East Docks (46 Slips) at Sudden Valley Marina	l.



Reference #	Description	Total	
1.0	General Requirements	\$100,415	
2.0	Demo East and West Floating Docks/ Fingers		\$85,520
3.0	Remove and Relocate Steel Pilings		\$66,240
4.0	Docks/ Fingers Materials, Coated Steel Fram	ne- (ScottCo)	\$519,110
5.0	Install Docks, Fingers and Decking		\$118,560
6.0	New Fire Standpipes		\$31,380
7.0	Gangway and Security Gates	\$18,715	
8.0	Water and Electrical Service at Slips	\$46,172	
9.0	Subtotal	\$986,112	
	Estimate Contingency at Conceptual Desi <sub>1</sub>	15%	<u>\$147,917</u>
10.0	Subtotal	\$1,134,029	
	Prime Contractor OHP	\$170,104	
11.0	TOTAL Budget Construction Price		\$1,304,133 Excludes Sales Taxes
ADD Alternate	For aluminum frame Docks/ Fingers ADD to	Above	\$1,050,000

#### **Basis of Estimate**

1 This estimate is based on Ashton Engineering Preliminary drawings dated 3.31.2024. Sheets 1, 2, 3.

2 Assume that wages for this project will be comparable to quality skilled contractors (comparable to union wages)

a. Wages for Laborer = \$50 (base with fringe) plus 30% for burden = \$65/ hour.

b. Wages for Operator = \$75 (base with fringe) plus 30% for burden = \$100/ hour.

c. Wages for Skilled Worker = 80 (base with fringe) plus 30% for burden = 105/ hour.

This is an Opinion of Probable Cost



4.24.2023 Revised to include electrical and water at fingers.

Ashton Engineering, Inc.

Preliminary Design Budgetary Estimate

Rory Woolsey, CEP



SPECIFICS: Replace Floating West Docks (46 Slips) and East Docks (46 Slips) at Sudden Valley Marina.

#### **Basis of Estimate**

- 3 Building permits and fees are NOT included in this estimate.
- 4 This estimate excludes sales taxes.
- 5 This estimate excludes Architect and Engineer Fees.
- 6 A 15% estimate contingency has been added due to conceptual design.

#### **Execution of this work**

- 7 Specialty contractor will perform this work acting as the prime contractor.
- 8 Step 1: Order docks/ fingers. Mobilization.
- 9 *Step 2:* Remove standpipe fire water.
- 10 Step 3: Remove standpipes, docks/ fingers.
- 11 Step 4: Remove and relocate 14 steel piles.
- 12 Step 5: Install new docks and fingers.
- 13 Step 6: Install new standpipes.
- 14 Step 7: Gangways improvements and Electrical.
- 15 Step 8: Demobilization.



	Sudder	Note:	arina Rep nis is an Opinion		2	am, wa
em #	Description	Quantity	Units	Unit Cost	Extended	Estimate Notes
1.0	General Requirements					
	Project Duration = 14 Weeks (Mob 1 Wk, Demo Fire Pipe 1 Wk, Demo	Docks 2 Wks, Move 1	Piles 2 Wks, Install D	ocks 3 Wks, Standp	oipes 2 Wks, Gangwa	ny/ electric 1 Wks, Demo 1 Wks)
	Engineering, Permits/ Fees					
1	Permits/ Fees	1	Not included	0.00	\$0	
2	Engineering Design Fee	1	Not included	0.00	\$0	
3	T.E.S.C. Plan and Implementation	1	Allwance	2,500.00	\$2,500	
	Mobilize and Site Set Up					
4	Contractor mobilize to site	12	Crew hours	335.00	\$4,020	Crew = \$335/ crew hour
5	Temporary fence: establish laydown and work areas	500	LF	6.75	\$3,375	
6	Temp toilet	14	Weeks	80.00	\$1,120	
7	Temp site trailer- superintendent	14	Weeks	125.00	\$1,750	Small trailer
8	Small dumpster on site	14	Weeks	455.00	\$6,370	for duration of project w/ weekly pick up
	Site Management					
9	Prime (Specialty) Contractor superintendent	560	Lhours	110.00	\$61,600	Full time
10	Prime General Laborer- daily site clean up	140	Lhoours	65.00	\$9,100	
	Insurance					
11	Site specific insurance for this project	14	Weeks	250.00	\$3,500	
	Close Out and Turnover					
	Final site cleanning	12	Crew hours	130.00	\$1,560	Crew = \$ 130/ crew hour
	Turnover to client & punchlist	1	LS	1,500.00	\$1,500	
14	Demobilize equipment and labor	12	Crew Hours	335.00	\$4,020	
	TOTAL				\$100,415	
2.0	Demo East and West Floating Docks/ Fingers					
	Remove Dry Standpipe System					
1	Shut off water	2	Crew Hours	105.00	\$210	
2	Disconnect 4" at flange at gangway- 2 locations	2	Crew Hours	275.00	\$550	Crew = Skilled \$210 laborer \$65 = \$275 per crew hour
3	Remove standpipe assemblies- 4 assemblies	4	Crew Hours	275.00	\$1,100	-
4	Remove 4" pipe- 405 LF	12	Crew Hours	275.00	\$3,300	
5	Remove hanger assemblies 10 Each	8	Crew Hours	275.00	\$2,200	Salvage if possible
6	Load truck for recycle/ dump	12	Crew Hours	130.00	\$1,560	Crew = laborers = \$130/ crew hour
0	Load truck for recycle/ dullip	12	CIEW HOURS	150.00	\$1,500	$c_1c_w = abbrois = \phi_1 J 0/ brow hour$



This is an Opinion of Probable Cost

ltem #	Description	Quantity	Units	Unit Cost	Extended	Estimate Notes
8	Load truck for recycle/ dump	1	LS	1,500.00	\$1,500	Salvage if possible
	Fingers Demolition- assume 3' x 18' x 2' depth x 52 each					
9	Disconnect fingers at triangle; 100 Triangles disconnect	24	Crew Hours	275.00	\$6,600	Crew = 2 skilled \$210 Laborer \$65 = \$275/ Crew hour
10	Crane or Boat fingers to shore (104 structures)	32	Crew Hours	520.00	\$16,640	Crew = Operators \$200 crane \$75 boat \$50 labor \$195 = \$520/ Crew hour
11	Load fingers on truck	16	Crew Hours	305.00	\$4,880	Crew = Operator \$100 crane \$75 laborers \$130 = \$305/ Crew hour
12	Haul fingers for recycle/ disposal	24	Truck Hours	185.00	\$4,440	Volume = 5,616 CF Weight = 28 tons for 52 fingers
13	Dump fee	28	Tons	100.00	\$2,800	
	Docks Demolition assume- 6' x 10' x 2' x 560 LF					
14	Disconnect docks; assume docks one connection per dock = 56 each	32	Crew Hours	275.00	\$8,800	Crew = 2 skilled \$210 Laborer \$65 = \$275/ Crew hour
15	Crane or Boat docks to shore (56 structures)	32	Crew Hours	520.00	\$16,640	Crew = Operators \$200 crane \$75 boat \$50 labor \$195 = \$520/ Crew hour
16	Load docks on truck	16	Crew Hours	305.00	\$4,880	Crew = Operator \$100 crane \$75 laborers \$130 = \$305/ Crew hour
17	Haul docks for recycle/ disposal	24	Truck Hours	185.00	\$4,440	Volume = 6,720 CF Weight = 35 tons for 56 each docks 6' x 10' x 8"
18	Dump fee	35	Tons	100.00	\$3,500	
	TOTAL				\$85,520	
3.0	Remove and Relocate Steel Pilings					
	°					
	Mobilize Pile Driving and Set Up					
1	<b>Mobilize Pile Driving and Set Up</b> Moilize set up for pulling and driving piles	1	LS	7,500.00	\$7,500	
1		1	LS	7,500.00	\$7,500	
1 2	Moilize set up for pulling and driving piles	1 24	LS Crew Hours	7,500.00 915.00	\$7,500 \$21,960	Foreman \$120 Skilled \$360 Operator \$125 Equipment \$310 = \$915/ Crew
	Moilize set up for pulling and driving piles Remove Piles (14 Each) Assume 15' Embedment	-			ŕ	Foreman \$120 Skilled \$360 Operator \$125 Equipment \$310 = \$915/ Crew
	Moilize set up for pulling and driving piles <b>Remove Piles (14 Each) Assume 15' Embedment</b> Piles removed, 14 Each x 15' = 210 LF	-			ŕ	
2	Moilize set up for pulling and driving piles <b>Remove Piles (14 Each) Assume 15' Embedment</b> Piles removed, 14 Each x 15' = 210 LF <b>Place Piles in New Loaction (14 Each)</b>	24	Crew Hours	915.00	\$21,960	
2 3	Moilize set up for pulling and driving piles <b>Remove Piles (14 Each) Assume 15' Embedment</b> Piles removed, 14 Each x 15' = 210 LF <b>Place Piles in New Loaction (14 Each)</b> Piles driven at new location	24 32	Crew Hours Crew Hours	915.00 915.00	\$21,960 \$29,280	
2 3	Moilize set up for pulling and driving piles <b>Remove Piles (14 Each) Assume 15' Embedment</b> Piles removed, 14 Each x 15' = 210 LF <b>Place Piles in New Loaction (14 Each)</b> Piles driven at new location Demobilize	24 32	Crew Hours Crew Hours	915.00 915.00	\$21,960 \$29,280 \$7,500	Foreman \$120 Skilled \$360 Operator \$125 Equipment \$310 = \$915/ Crew Foreman \$120 Skilled \$360 Operator \$125 Equipment \$310 = \$915/ Crew
2 3 4	Moilize set up for pulling and driving piles <b>Remove Piles (14 Each) Assume 15' Embedment</b> Piles removed, 14 Each x 15' = 210 LF <b>Place Piles in New Loaction (14 Each)</b> Piles driven at new location Demobilize <b>TOTAL</b>	24 32	Crew Hours Crew Hours	915.00 915.00	\$21,960 \$29,280 \$7,500	
2 3 4	Moilize set up for pulling and driving piles <b>Remove Piles (14 Each) Assume 15' Embedment</b> Piles removed, 14 Each x 15' = 210 LF <b>Place Piles in New Loaction (14 Each)</b> Piles driven at new location Demobilize <b>TOTAL</b> <b>Docks/ Fingers Materials, Coated Steel Frame- (ScottCo)</b>	24 32	Crew Hours Crew Hours	915.00 915.00	\$21,960 \$29,280 \$7,500	



This is an Opinion of Probable Cost

[tem #	Description	Quantity	Units	Unit Cost	Extended	Estimate Notes
3	Foam filled floats at east and west - Docks	84	Each	450.00	\$37,800	
	<b>Floating Fingers - Material</b> (52 Each x 18' = 936 LF total fingers le	ngth)				
4	3' x 10' truss frame at east and west - (3' x 18' Fingers x 48 Ea)	48	Each	740.00	\$35,520	Includes Poly Urea Coating
5	3' x 8' custom truss frame- Fingers	48	Each	740.00	\$35,520	
6	3' x 5' Foam filled floats- Fingers	48	Each	300.00	\$14,400	
7	3' x 4' Foam filled floats- Fingers	48	Each	240.00	\$11,520	
8	3' x 2' Foam filled floats- Fingers	48	Each	150.00	\$7,200	Includes Poly Urea Coating
9	4' x 10' truss frame -(4' x 18' Fingers x 4 Each)	2	Each	820.00	\$1,640	
10	4' x 8' custom truss frame- Fingers	2	Each	910.00	\$1,820	
11	4' x 5' Foam filled floats- Fingers	2	Each	390.00	\$780	
12	4' x 4' Foam filled floats- Fingers	2	Each	300.00	\$600	
13	4' x 2' Foam filled floats- Fingers	2	Each	175.00	\$350	
14	5' x 10' truss frame - (5' x 18' Fingers x 2 Each)	2	Each	1,050.00	\$2,100	Includes Poly Urea Coating
15	5' x 8' custom truss frame- Fingers	2	Each	1,000.00	\$2,000	
16	4' x 5' Foam filled floats- Fingers	8	Each	375.00	\$3,000	
17	3' x 5' Foam filled floats- Fingers	2	Each	305.00	\$610	
	Accessories					
18	4' x 4' triangle truss frames	86	Each	435.00	\$37,410	Possibly use existing triangle frames
19	4' x 4' triangle including pile guide	14	Each	685.00	\$9,590	
20	2" x 10' recycled fascia lumber	1	LS	45,650.00	\$45,650	
21	Corner bumper, Pile guides, edging	1	LS	10,527.00	\$20,000	
	Decking Material 1" Deep Micromesh					
22	Dock area = 3,480 SF (assumes 100% of dock area coverage)	3,480	SF	25.50	\$88,740	Includes waste
23	Fingers area = 2,900 SF (assumes 100% grated fingers deck)	2,900	SF	25.50	\$73,950	
	Shipping					
24	Shipping structues, floats for docks and fingers from Idaho	1	LS	8,000.00	\$8,000	
25	Shipping to site decking materials from Kent	1	LS	2,800.00	\$2,800	
	Unload and Stack all Materials on Site					
26	Unload trucks and stack at site	16	Crew Hours	420.00	\$6,720	Crew = Operator \$100 crane/ forklift \$125 Laborers \$195 = \$420/ Crew Ho
	TOTAL				\$519,110	

# Sudden Valley Marina Replacement, Bellingham, Wa This is an Opinion of Probable Cost Description Quantity Unit Cost Extended Estimate Notes

# 5.0 Install Docks, Fingers and Decking

	Assemble Docks and Fingers and set in Water		_			
1	Assemble foam filled floats with dock structures (59 Frames)	24	Crew Hours	460.00	\$11,040	Crew = Operator \$100 crane/ forklift \$125 skilled \$105 laborers \$130 = \$46
2	Assemble foam filled floats with finger structures (104 frames)	24	Crew Hours	460.00	\$11,040	Crew = Operator \$100 crane/ forklift \$125 skilled \$105 laborers \$130 = \$46
	Float Docks into Place and Fasten					
3	Set docks into place w/ boats or crane (59 Each)	32	Crew Hours	520.00	\$16,640	Crew = Operators \$200 crane \$75 boat \$50 labor \$195 = \$520/ Crew hour
4	Bolt up docks in place	40	Crew Hours	395.00	\$15,800	Crew = Skilled \$200 Labor \$195 = \$395/ Crew Hour
	Float Fingers into Place and Set Triangle					
5	Set fingers into place w/ boats or crane (104 Each)	32	Crew Hours	520.00	\$16,640	Crew = Operators \$200 crane \$75 boat \$50 labor \$195 = \$520/ Crew hour
6	Bolt triangle structures in place (100 Each)	48	Crew Hours	395.00	\$18,960	Crew = Skilled \$200 Labor \$195 = \$395/ Crew Hour
	Install Decking (6,380 SF)					
7	Place decking and fasten	72	Crew Hours	395.00	\$28,440	Crew = Skilled \$200 Labor \$195 = \$395/ Crew Hour
	TOTAL				\$118,560	

#### 6.0 New Fire Standpipes

ISHTON

Item #

Pipe Hangers	Pipe	Hangers
--------------	------	---------

1	Pipe hanger materials	8	Hangers	350.00	\$2,800	Partially salvaged
2	Install pipe hangers at new dock	16	Crew Hours	275.00	\$4,400	Crew = skilled \$210 laborer \$65 = \$275/ Crew hour
	4" Pipe Installed					
3	4" pipe materials & fittings- material	410	LF	12.00	\$4,920	
4	Installing Pipe & fittings -labor	32	Crew Hours	275.00	\$8,800	Crew = skilled \$210 laborer \$65 = \$275/ Crew hour
	Standpipe Assemblies					
5	Standpipe assemblies- Material	4	Assemblies	1,200.00	\$4,800	Includes loop
6	Install standpipe assemblies	12	Crew Hours	275.00	\$3,300	Crew = skilled \$210 laborer \$65 = \$275/ Crew hour
	Startup and Test					
7	Connection at shoreline 2 each	4	Crew Hours	275.00	\$1,100	
8	Startup and test	6	Crew Hours	210.00	\$1,260	Crew = skilled \$210
	TOTAL				\$31,380	

ASHTOP Engineering, In Coastal & Structural Des	Sudden Valley Marina Replacement, Bellingham, Wa This is an Opinion of Probable Cost							
Item #	Description	Quantity	Units	Unit Cost	Extended	Estimate Notes		
7.0	Gangway and Security Gates							
	Gangways							
1	Reset existing gangway at the east dock	4	Crew Hours	410.00	\$1,640	Crew = Operator \$100 crane \$75 skilled \$105 labor \$130 = \$410/ Crew hou		
2	New ADA gangway at west dock 4' x 35' long- Material	35	Linear Feet	345.00	\$12,075	ADA ramp with handrail		
3	Set new ADA gangway	6	Crew Hours	410.00	\$2,460			
4	Concrete topping at new at abutement	30	SF	30.00	\$900			
	Relocate/ reuse Security Gates							
5	Relocate security gates at east and west	4	Crew Hours	410.00	\$1,640			
	TOTAL				\$18,715			
8.0	Water and Electrical Service at Slips							
	Trenching From Restroom to Docks (Electrical & Water in same	trench)						
1	Private locates prior to trenching	1	LS	840.00	\$840	Private locates		
2	Trench excavate 2' x 2' depth x $530' = 40$ CY	5	Crew Hours	240.00	\$1,200	Operator \$100 laborer \$65 equipment \$75 = \$240 per crew hours		
3	Haul spoils	6	Truck Hours	185.00	\$1,110			
4	Dump spoils	30	Tons	15.00	\$450			
5	Sand base for pipe/ conduit in trench- Material	30	CY	35.00	\$1,050			
6	Trucking base to jobsite	4	Truck Hours	185.00	\$740			
7	Place sand base for pipe/ conduit	4	Crew Hours	240.00	\$960	Operator \$100 laborer \$65 equipment \$75 = \$240 per crew hours		
	Water and Conduit Pipe in Trench							
8	3/4" HDPE pipe in trench- Material	530	LF	1.00	\$530			
9	1" conduit in trench- Material	530	LF	2.00	\$1,060			
10	Setting water pipe and conduit in trench	8	Crew Hours	275.00	\$2,200	2 Skilled \$210 1 laborer \$65 = \$275/ Crew Hours		
	Backfill Electrical/ Water Trench							
11	Backfill trench with native material	6	Crew Hours	240.00	\$1,440	Operator \$100 laborer \$65 equipment \$75 = \$240 per crew hours		
	Valve Box and Water Service at Docks							
12	Connect water line to existing service at restroom	1	Connection	1,500.00	\$1,500	Use existing meter		
13	Install water valve and valve box at docks -2 Each	2	Each	1,200.00	\$2,400			
	Water Extension from Service Valve to end of Docks							

#### 4/24/2023



This is an Opinion of Probable Cost

Item #	Description	Quantity	Units	Unit Cost	Extended	Estimate Notes
14	3/4" HDPE pipe to end of docks east and west (290' + 290')	580	LF	1.00	\$580	
15	Hangers for hanging pipe at docks- Material	12	Hanger Assemblies	150.00	\$1,800	Prefabicated
16	Hanger assemblies at docks- Labor	12	Crew Hours	275.00	\$3,300	2 Skilled \$210 1 laborer \$65 = \$275/ Crew Hours
17	Double hose bibbs	12	Each	120.00	\$1,440	
	Electrical Panel and Service at Docks					
18	Connection to panel at restrooms	4	Crew Hours	290.00	\$1,160	Crew = 2 electricians \$290 per crew hour
19	Breaker panels at gangway to each dock- Material	2	Each	750.00	\$1,500	
20	Breaker panels at gangway to each dock- Labor	6	Crew Hours	290.00	\$1,740	Crew = 2 electricians \$290 per crew hour
	Electrical Service to Outlets at Docks					
20	Conduit and wire to each slip	580	LF	10.40	\$6,032	
21	Hangers for hanging conduit- Material	12	Each	150.00	\$1,800	Prefabricated
22	Hanger assemblies at docks- Labor	12	Crew Hours	275.00	\$3,300	2 Skilled \$210 1 laborer \$65 = \$275/ Crew Hours
23	GFCI 15 Amp outlets boat slips	48	Each	150.00	\$7,200	
	Testing					
24	Test water service to docks	2	Crew Hours	210.00	\$420	2 skilled = \$210/ Crew Hour
25	Test electrical to docks	2	Crew Hours	210.00	\$420	
	TOTAL				\$46,172	

## Sudden Valley Community Association

### Marina Dock Replacement

PNW Estimate - Bid Package, Permitting, and Construction Management

Task	Description	Hours	Est	imated Cost
Design Oversight				
	Oversight of Ashton Engineering, and coordination with SVCA.	16		
	Total Estimated Design Oversight Hours	16	\$	2,160.00
Permitting				
	Oversight of permit applications, and facilitate signatures with SVCA.	16		
	Total Estimated Permitting Cost	16	\$	2,160.00
Contractor Bids				
	Prepare and issue RFQ to contractors. Answer any contractor questions, and prepare			
	recommendation to SVCA.	8		
	Total Estimated Bid Package Hours	8	\$	1,080.00
Construction Management				
	Oversight of construction process. Ashton Engineering is assumed to be lead oversight.	40		
	Total Estimated Construction Management Hours	40	\$	5,400.00
	Total Estimated		\$	10,800.00

## **Technical Memorandum**



# SVCA 10-Year Capital Plan 2023 & 2024 Projects

June 30<sup>th</sup>, 2023

Tyler Andrews PNW Services, Inc. PO Box 30498 Bellingham, WA 98228

Re: Technical Memorandum

SVCA 10-Year Capital Plan, 2023 Culvert Projects & 2024 Culvert/Road Projects.

The purpose of this Technical Memorandum is to give recommendations for the 2023 and 2024 infrastructure improvement projects and to give a preliminary cost estimate as a means to review the planned yearly budget amounts. Based on Impact Designs completed field investigation of the Sudden Valley Community Association roadway and drainage infrastructure for the 10-year Capital Improvements project, we found a total of 58 drainage culverts that appear to be in critical condition.

#### 2023 Culvert Projects:

The following 10 culverts were found to be in the greatest critical condition and are recommended to be replaced this year. We estimate each project will have a cost of approximately \$10,000 - \$15,000 each depending on material/diameter/length. This gives a project budget range of \$100,000 - \$150,000 total.

Culvert ID	Zone Number	Road Name	Approximate Address	Culvert Length (ft.)	Culvert Diameter (in.)	Culvert Material
11	Zone 5	Big Leaf Ln	15 Big Leaf Ln	55	18/12	СМР
15	Zone 5	Shetland Ct	19 Tumbling Water Dr	58	12	СМР
17	Zone 5	Shetland Ct	3 Shetland Ct	41	18	СМР
FND 13	Zone 13	Yearling Pl	5 Meadow Ct	28	12	СМР
28	Zone 13	Granite Cir	67 Polo Park Dr	46	24	СМР
403	Zone 9	Polo Park Dr	230 Polo Park Dr	59	18	СМР
162	Zone 3B	Kinglet Ct	188 Sudden Valley Dr	41	12	CMP
FND 67	Zone 1	Gate 1 Mailboxes	Gate 1 Mailboxes	39	12	СМР
63	Zone 2	Lake Louise Dr	52 Lake Louise Dr	70	18	CMP
408.2	Zone 2	Larkspur Ct	7 Larkspur Ct	17	12	СМР

#### 2024 Culvert Projects:

The following 48 culverts were all found to have a critical barrel condition and should be prioritized for the 2024 maintenance projects. All the culverts below appear to be simple conveyance pipes for roadway crossings, and do not have fish bearing capacity. We estimate each project will cost approximately \$10,000 - \$15,000 each depending on material/diameter/length. This gives a project a budget range of \$490,000 - \$735,000 total.

Culvert ID	Zone Number	Road Name	Approximate Address	Culvert Length (ft.)	Culvert Diameter (in.)	Culvert Material
66	Zone 5	Louis View Dr	20 Louise View Dr	62	18	СМР
67	Zone 5	Sweetclover Cir	12 Sweetclover Cir	48	12	Inlet-Concrete Pipe/Outlet- CMP
58	Zone 5	Louis View Dr	1 Catkin Ct	48	12	СМР
1	Zone 13	Polo Park Dr	150 Polo Park Dr	54	18	СМР
78	Zone 13	Sunnyside Ln	29 Sunnyside Ln	50	18	СМР
431	Zone 13	Lost Lake Ln	29 Lost Lake Ln	75	18	СМР
27	Zone 13	Misty Ridge Ct	66 Polo Park Dr	39	12	СМР
404	Zone 9	Polo Park Dr	230 Polo Park Dr	79	18	СМР
205	Zone 3A	Spring Rd	15 Spring Rd	40	24	СМР
406	Zone 3A	Rocky Ridge Dr	30 Rocky Ridge Dr	109	12	СМР
171	Zone 3B	Stable Ln	32 Stable Ln	32	12	СМР
178	Zone 3B	Canyon Ct	23 Canyon Ct	39	12	СМР
176	Zone 3B	Tawny Cir	24 Lost Fork Ln	50	12	СМР
432 433	Zone 3B	Strawberry Cyn Ct	13 Strawberry Cyn Ct	46	12 18	СМР
103	Zone 3C	Amberland Way	142 Harbor View Dr	42	24	СМР
99	Zone 3C	Plum Ln	28 Plum Ln	51	12	CMP
214	Zone 3C	Maple Ct	46 Maple Ct	67	18	CMP
126	Zone 3D	Sudden Valley Dr	1 Sudden Valley Dr	120	18/12	CMP/CPP
89	Zone 3D	Indian Ridge Ct	39 Sudden Valley Dr	86	12	СМР
FND 38	Zone 3D	Indian Meadow Ct	1 Indian Meadow Ct	35	12	СМР
118	Zone 3D	Harbor View Dr	46 Harbor View Dr	43	18	СМР
117	Zone 3D	Harbor View Dr	54 Harbor View Dr	35	18	СМР
120	Zone 3D	Harbor View Dr	10 Harbor View Dr	42	18	СМР
FND 30	Zone 3D	Harbor View Dr	99 Harbor View Dr	39	18	СМР
109	Zone 3D	Green Hill Rd	55 Green Hill Rd	41	18	CPP/CMP
111	Zone 3D	Harbor View Dr	113 Harbor View Dr	40	18	СМР
122	Zone 3D	Rocky Ridge Dr	2 Rocky Ridge Dr	29	18	СМР
FND 48	Zone 1	Par Ln	20 Par Ln	55	12	СМР
147	Zone 1	Par Ln	20 Par Ln	20	12	СМР

Impact Design, 5426 Barrett Road, Ferndale WA 98248 cell: (360) 389-8138 email: scott@bold-impact.com

1						
441	Zone 1	Jubilee Ln	3 Jubilee Ln	59	12	СМР
148	Zone 1	Par Ln	11A Par Ln	189	12	СМР
415	Zone 1	Birdie Ln	28 Windward Dr	53	12	СМР
143	Zone 1	Inlet Cir	26 Longshore Ln	82	12	СМР
144	Zone 1	Inlet Cir	26 Longshore Ln	31	12	CMP
145	Zone 1	Spinnaker Ln	17 Marina Dr	72	12	CPP/CMP
FND 49	Zone 1	Marina Dr	17 Marina Dr	40	12	CMP
157	Zone 1	North Point Dr	5 North Point Dr	30	12	Green PVC/CMP
FND 52	Zone 1	Sanwick Pt Ct	36 North Point Dr	43	12	Concrete Pipe/CPP
81	Zone 2	Lake Louise Dr	1 Sparrow Ct	61	18	СМР
408.1	Zone 2	Larkspur Ct	7 Larkspur Ct	19	12	CMP
409	Zone 2	Whispering Cedars	Whispering Cedars Entrance	N/A	24	СМР
410	Zone 2	Lake Louise Dr	22 Lake Louise Dr	120	12	СМР
203	Zone 2	Lake Louise Dr	14 Lake Louise Dr	61	18	СМР
FND 61	Zone 2	Marigold Dr	37-30 Marigold Dr	283	12	CMP
75	Zone 2	Marigold Dr	43 Marigold Dr	40	12	СМР
FND 45	Zone 2	Sunflower Cir	23 Sunflower Cir	20	12	СМР
445	Zone 2	Lake Louise Dr	20 Lake Louise Dr (Outlet)	200	12	СМР
FND 62	Zone 2	Barn View Ct	3 Barn View Ct	83	12	СМР

#### 2024 Road Projects:

Impact Design recommends that in addition to drainage improvement projects, at least one major asphalt overlay road project should be considered yearly. For the 2024 construction season Impact Design recommends Deer Run Lane should be overlayed. We estimate overlay projects will cost \$4.00 - \$5.00 per square foot. This gives the overlay of Deer Run Lane a project budget range of \$180,000 - \$225,000.

#### **Overall Conclusions**

Should all culvert and roadway projects we have recommended for the 2024 construction season be completed, we estimate the total costs to be in the \$670,000 - \$960,000 range. The cost estimate per culvert replacement, and cost per square foot of asphalt overlay is based on local historical data alone, and no engineered design has been done. Prior to construction, an engineering analysis and civil/stormwater engineering drawings should be completed. Based on this analysis a yearly budget of \$900,000 to \$1,000,000 appears to be adequate to catch up with and maintain SVCA's infrastructure for the next 3-5 years.

Based on our current progress we expect to have the first draft of the SVCA 10-Year Capital Improvements Plan by the end of August.

Impact Design, 5426 Barrett Road, Ferndale WA 98248 cell: (360) 389-8138 email: scott@bold-impact.com Respectfully,



6-30-2023

Scott Goodall, MS, PE Principal Impact Design, LLC